



CONTRACTOR SHALL INSTALL AIRLOCK  
TO WORK AREA ENTRANCE  
(SEE NOTE 6)

**1 WTC**  
**TYPICAL MECHANICAL FLOOR SETBACKS**  
**7th FLOOR, 41st FLOOR and 70th FLOOR**  
**[2 WTC SIMILAR EXCEPT INTAKE FANS ON EAST & WEST SIDES]**

CONTRACTOR SHALL INSTALL AIRLOCK  
TO WORK AREA ENTRANCE

CONTRACTOR SHALL SEAL DRAIN  
PRIOR TO REMOVAL (TYP.)

(TYP.)



**NOTES**

1. A REMOTE DECONTAMINATION CHAMBER SHALL BE PROVIDED IN EACH BUILDING AT A LOCATION REMOTE FROM THE WORK AREA.
2. WATER, DRAIN AND ELECTRICAL SERVICES SHALL BE MAINTAINED ON SITE AND IS SUBJECT TO THE CONTRACTOR'S RESPONSIBILITY.
3. REMOVE ALL BUILT-UP ROOF MATERIAL AND DISPOSE AS ASBESTOS WASTE.
4. AFTER EACH SEQUENCE OF WORK, PROVIDE PROTECTION TO THE BUILDING OR EQUIVALENT.
5. THE CONTRACTOR SHALL SEAL ALL COMMUNICATING OPENINGS, ROOF LEVEL OF THE IMMEDIATE ADJACENT BUILDING BEYOND.
6. ENTRANCE TO ROOF SETBACKS SHALL BE PROVIDED AT THE CORNERS OF THE FLOOR IN THE NORTHWEST, SOUTHWEST AND SOUTHEAST CORNERS.

**LEGEND**

- BOUNDARY
- [Hatched Box] BUILT-UP ROOF
- (X) ROOF DRAIN

ALL DIMENSIONS SHALL MATCH 100  
DATE: 10-1-94